



August 25, 2015

Jeff Morris
 Assistant Fire Chief
 Eules Fire Department
 Email: jmorris@eulesstx.gov

Quote #9702D

Chief Morris,

Per your request we are quoting remounting & refurbishing your Frazer Type I 12' Generator Powered Module, X-507 (E-1193), onto a 2016 Ford F-350 6.7L diesel chassis. For your convenience all pricing has been itemized below.

2016 Ford F-350 6.7L diesel chassis (order Ford red)	\$ 40,500.00
Heat shielding for diesel chassis	\$ 1,500.00
Granning air suspension (wired to dump without ignition ON , and set to partial refill)	\$ 6,700.00
Remount of Module (see Incl. items below)	\$ 15,000.00
Chassis Exterior Upgrades	\$ 1,575.00
Chassis Interior Upgrades	\$ 1,400.00
Module Exterior Upgrades	\$ 23,050.00
Module Interior Upgrades	\$ 11,625.00
HGAC Fee	\$ 600.00
Total	\$ 101,950.00

Chassis Exterior Upgrades

1. Items included in remount fee:
 - a) Ranch Hand powder coated grille guard \$ Incl.
Note – Inspect grille guard prior to installation
 - b) Frazer aluminum rear window pass through plate \$ Incl.
 - c) (2) Mega fuses with new wiring \$ Incl.
 - d) Mounting rubber \$ Incl.
 - e) Make old chassis road ready \$ Incl.
2. No striping or lettering on chassis \$ N/C
3. Furnish and install (2) Whelen SA314B speakers in lieu of standard \$ 350.00
4. Furnish & install (2) Whelen M7 split red/clear grille lights with clear lenses in lieu of furnishing (2) Whelen M4 lights, set each light to a different flash pattern
Layout: Clear/Red – Red/Clear \$ 225.00
5. Furnish & install (2) Whelen M7 split red/clear intersects lights with clear lenses in lieu of furnishing (2) Whelen M4 lights, set each light to a different flash

Quote #9702D

pattern

Layout: Clear/Red – Red/Clear

Note – Intersects will be installed in line with center cross beam of grille guard	\$	225.00
6. Furnish & install stainless steel wheel covers	\$	450.00
7. Remove & reinstall (1) BP200-EF speaker centered in the grille guard between your Whelen speakers, this will be used for EQ2B siren	\$	225.00
8. Install your black nerf bars on chassis	\$	100.00
9. Route chassis exhaust to under generator compartment	\$	N/C
Total	\$	1,575.00

Chassis Interior Upgrades

10. Items included in remount fee:		
a) Furnish & install powder coated aluminum six position console	\$	Incl.
Note – Certain charges apply for labor required to remove & reinstall		
11. Front of Console – Remove & reinstall self contained radio with existing coax, with speaker on floor		
Note – Wire large wire Battery hot & 2 nd smaller wire ignition hot	\$	300.00
12. Slot 1 – Furnish & install Whelen 295SLSA1 siren	\$	Incl.
13. Slot 2/3 – Furnish & install (1) new double switch panel with new switches <i>Layout: Primary, Secondary, Blank, Opticom, Blank, Blank, Blank</i> <i>Interior Lights, Rear Load, Side Scene, Side Scene, Start/Stop</i>	\$	Incl.
14. Slot 4 – Remove & reinstall EQ2B control head	\$	300.00
15. Slot 5 – Remove & relocate (2) portable radio chargers to a modified plate Note – Plate should appear as X-910	\$	225.00
16. Slot 6 – Remove & reinstall Knox key secure mounted to single plate, wire ignition hot Note – Remove Knox face plate prior to delivery	\$	200.00
17. Rear of Console – Remove and reinstall dual map holder	\$	25.00
18. Remove and reinstall (1) large glove box holder on rear wall of chassis cab	\$	25.00
19. Remove & reinstall LIND power supply inside console Note – Wire Battery Hot and push power cord through front of console	\$	125.00
20. Furnish & install arm rests on console	\$	200.00
21. Do not remove laptop docking station from old chassis	\$	N/C
Total	\$	1,400.00

Module Exterior Upgrades

22. Items included in remount fee:		
a) Install ignition & fail safe solenoids on electrical shelf	\$	Incl.
b) Full electrical check	\$	Incl.
c) Generator system check & inspect all generator cabling, replace as needed	\$	Incl.
d) Rewire tail lights	\$	Incl.
e) New passthrough rubber boot	\$	Incl.
f) New ribbed rubber in compartments	\$	Incl.
g) Replace all door compartment bumpers	\$	Incl.
h) Replace weather stripping on compartment and entry doors	\$	Incl.
i) Time save exterior compartment panels	\$	Incl.

j) Add new insulation to side & rear entry doors	\$	Incl.
k) Replace entry door windows with double pane windows	\$	Incl.
l) Replace side entry door-open spring, do not install gas shock	\$	Incl.
23. No striping or lettering on module	\$	N/C
24. Removal of rear conspicuity prior to paint		
Note – When repainting a module it is necessary to remove exterior conspicuity, failure to do so will result in bleeding of new paint under existing conspicuity	\$	650.00
25. Furnish & install 3M diamond grade fluorescent lime yellow conspicuity with translucent red overlay on entire rear wall including entry doors	\$	1,500.00
26. Remove number from existing plate on front wall	\$	Incl.
27. Furnish & install 3 steel placard holders, with unit number M552		
<i>Location: O2 compartment door centered from front to back and 1" above vent, front I/O centered front to back, and above the belt line stripe and latch, front wall driver side</i>	\$	250.00
28. Stripe, prime, and repaint 12' Module Ford red (FA90:F1) including outer edge of outer roof trim, in addition paint entry door jambs white	\$	6,500.00
Note – Items sub-listed (a-k) are included with paint unless stated otherwise		
a) Strip, prime, and repaint roof on module Ford white (FA:90:YO)	\$	Incl.
b) Furnish & install painted corner caps on module		
Note – Vertical edge will be painted Ford red (FA90:F1) & top edge will be painted Ford white (FA:90:YO)	\$	Incl.
c) Furnish & install new side entry door with new style powder coated panels	\$	Incl.
d) Furnish & install new rear entry doors with new style powder coated panels	\$	Incl.
e) Furnish & install stainless threshold on rear storage compartment	\$	Incl.
f) Replace compartment and entry door latches keyed J236	\$	Incl.
g) Replace marker lights	\$	Incl.
h) Remove & reinstall rear bumper	\$	Incl.
i) Remove & reinstall treadbrite panels	\$	Incl.
j) Remove and ship loose all listed emergency lighting below with chrome flanges		
1. Remove (8) Whelen 900 series red box lights	\$	Incl.
2. Remove (5) Whelen 900 series front wall lights	\$	Incl.
3. Remove (3) Whelen 900 series rear wall lights	\$	Incl.
4. Remove (2) Whelen 508 clear load lights	\$	Incl.
5. Remove (2) Whelen 600 series rear BTT	\$	Incl.
k) Remove & reinstall (2) 300 watt Quartz halogen side scene lights	\$	Incl.
Note – Wired to 2 switches on the console		
29. Furnish & install new rear entry door grabbers (discard old)	\$	Incl.
30. Furnish & install Cast LED license plate light (discard old)	\$	50.00
31. Clear lenses on listed emergency lights	\$	N/C
32. Enable Half Power feature on all emergency lights and wire to high/low switch on console	\$	1,100.00
33. Set every light to a completely different flash pattern	\$	Incl.
34. Furnish & install (8) Whelen M9 series red LEDs corner box lights with converter flanges	\$	2,600.00
35. Furnish & install (5) Whelen M9 series LEDs on front wall with converter flanges		
<i>Front Layout: Blue – Red – Clear – Red – Blue</i>	\$	1,625.00

36. Furnish & install (3) Whelen M9 series LEDs on rear wall with converter flanges <i>Rear layout: Amber – Amber – Amber</i>	\$	975.00
37. Furnish & install (2) Whelen M9 series LEDs BTT with chrome converter flanges	\$	600.00
38. Furnish & install (2) Whelen M9 series load lights with converter flanges on rear of module, wired to come ON with reverse, furnish switch	\$	800.00
39. Add catch cable to long lower compartment positioned on left side	\$	100.00
40. Use existing gas shock on front I/O compartment door, do not replace	\$	N/C
41. Furnish and install new gas shock on O2 compartment door	\$	150.00
42. Use existing gas shock on rear storage compartment door, do not replace	\$	N/C
43. Remove and reinstall existing Opticom and terminate to new chassis, wired OFF with driver side door park kill and on/off switch at console	\$	Incl.
44. Furnish and install 30A auto eject on front wall of module, add new cabling for 30A outlet, add access panel in O2 compartment and add plate over existing shore power outlet holdes (ship old loose)	\$	950.00
45. Furnish & install new Onan 5.5kW generator with non permeable hoses, emissions canister kit and add new 15 gal fuel tank and fuel pump ⁶ Note – Please remove Onan generator prior to delivery of remount to Frazer.	\$	5,200.00
46. Furnish and install new vents in long lower storage compartment	\$	Incl.
Total	\$	23,050.00

Module Interior Upgrades

47. Items included in remount fee:		
a) Reattachment of loose seat cushions	\$	Incl.
b) Replace all non-skid material on threshold(s) with black 3M non-skid material	\$	Incl.
c) Complete detail, if applicable		
1. Clean & wipe down lasco walls	\$	Incl.
2. Clean & wipe down floor of module	\$	Incl.
3. Clean & wipe down exterior & interior of cabinets	\$	Incl.
4. Clean & wipe down compartments and shelves	\$	Incl.
48. Furnish & install Onan buzzer kill switch at rear entry door with added plating	\$	250.00
49. Furnish & install rear load light switch at rear entry door	\$	125.00
50. Furnish & install new Lexan scratch resistant doors on all module cabinets (ship existing loose)	\$	775.00
Note – Do not use finger holes, use old stye U shaped slots		
51. Replace corner area counter top, front corner area wall and lower driver side wall all with stainless steel (discard old)	\$	750.00
52. Replace squad bench with stainless steel wrapper with new opening and frame for trash can (discard old)	\$	650.00
53. Furnish & install Engel 14qt. refrigerator with 120 VDC adapter and locking clasp ID 1864, on stationary portion of laydown O2 box, hard wire to fail-safe in electrical compartment	\$	950.00
54. Replace (8) fluorescent ceiling lights with (8) Grote LEDs (discard existing lights)	\$	3,000.00
55. Replace floor with new Alucabond subfloor and new Lonseal vinyl floor, reuse existing O2 box, replace thresholds, install black non-skid tap on top, install new	\$	3,000.00

cot plates and hook for Stryker Power-PRO (discard old flooring)			
56. Furnish & install 175-3 single position cot mount	\$	Incl.	
57. Remove & reinstall antler and bar	\$	N/C	
58. Furnish & install cobalt Wise corner trim	\$	300.00	
59. Leave A/C thermostat in existing location, do not move to action wall	\$	N/C	
60. Remove and velcro and residue from action wall countertop	\$	N/C	
61. Resecure front wall driver's side lasco panel	\$	N/C	
62. Furnish and install stainless trim on top and driver's side of Front I/O & Front corner area shelf	\$	150.00	
63. Furnish and install new seat belts at CPR seat & squad bench	\$	300.00	
64. Furnish and install screw cap covers on ceiling raceway, where missing	\$	N/C	
65. Furnish and install interior light on/off switch at rear entry door switch panel, and side entry door step well on forward wall	\$	350.00	
66. Furnish and install O2 outlet in ceiling raceway above patients chest area	\$	575.00	
67. Relocate A/C thermostat to action wall	\$	450.00	
	Total \$	11,625.00	

Terms and Conditions

1. Quote valid for 90 days.
2. All pricing is F.O.B. Houston.
3. Per TMVCC we are quoting this through our licensed franchise dealer, Sterling McCall Ford.
4. Please make your purchase order out to Sterling McCall Ford, 6445 Southwest Freeway Houston, TX 77074. Please email a copy of your purchase order and this quote to Pablo Cantu with Sterling McCall Ford at pcantu@sterlingmccallford.com and to Adam Fischer at sales@frazerbilt.com.
5. Payment for the entire purchase is due upon receipt and acceptance of completed unit.
6. Please remove the Onan generator prior to delivery at Frazer for remount.

Thank you for the opportunity to quote this job. If you have any questions please call me at 888-372-9371.

Best Regards,



Laura Richardson
Frazer, Ltd.

LGR:RR

Quote #9702D